



BNL-104021-2014-TECH

AGS.SN143;BNL-104021-2014-IR

Inspection Main Magnet Coil with Video Therm Portable Infrared System

M. H. Zguris

May 1983

Collider Accelerator Department
Brookhaven National Laboratory

U.S. Department of Energy

USDOE Office of Science (SC)

Notice: This technical note has been authored by employees of Brookhaven Science Associates, LLC under Contract No. DE-AC02-76CH00016 with the U.S. Department of Energy. The publisher by accepting the technical note for publication acknowledges that the United States Government retains a non-exclusive, paid-up, irrevocable, world-wide license to publish or reproduce the published form of this technical note, or allow others to do so, for United States Government purposes.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.


AGS STUDIES REPORTDate May 5, 1983Time 0700Experimenters Maintenance Group, M. Clancy, H. Farrell, E. Tombler, M.A. ZgurisReported by M.A. ZgurisSubject Inspection of Main Magnet Coil With Video Therm Portable Infrared SystemOBSERVATIONS AND CONCLUSION

A sweep of the main magnet coils with a Model LIC-84 Video Therm Camera was done with the AGS operating at a repetition rate of 3 sec, FT 1350 ms. The test results indicate that a normal operating temperature of 79°-85°F can be expected. The inspection group was able to distinguish a 2°F temperature difference in coil temperatures with the Therm Camera. A contact thermometer was then used to record the actual temperature of an indicated hot magnet. The results indicated five magnets were above 100°F: A6 - 100°F bottom (top coil); A5 - 108°F bottom (top coil); I17 - 112°F bottom (top coil); G20 - 125°F bottom (bottom coil); and C17 - 145°F bottom (bottom coil). Four coils were at 86°F A3, A4, A17 and A18. One coil was at 93°F (B4).


The five hot coils were backflushed during maintenance that day. In the future, after backflushing, a measured flow check will be made using a flow meter.

In conclusion, the group feels inspections with the Video Therm camera should be taken every three months with logging of coils with high temperature, plus the results of backflushing (flow check readings).


A video tape of the test is available with E. Tombler. The attached pictures show what coils look like, first when warm, second when hot and third when very hot.



79° - 85° F



6-10 125 F°



0-11 145 - F