

Beam Distribution Upstream of B Target

G. W. Bennett

May 1973

Collider Accelerator Department
Brookhaven National Laboratory

U.S. Department of Energy

USDOE Office of Science (SC)

Notice: This technical note has been authored by employees of Brookhaven Science Associates, LLC under Contract No.AT(30-1)-16 with the U.S. Department of Energy. The publisher by accepting the technical note for publication acknowledges that the United States Government retains a non-exclusive, paid-up, irrevocable, world-wide license to publish or reproduce the published form of this technical note, or allow others to do so, for United States Government purposes.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Objectives:

1. Measure beam distribution upstream of B station for DAS.
2. Cross comparison of IPDIC Units downstream of B.
3. Calibration of beam intensity monitor (split plate sum) at B.
4. Calibration of ion chamber beam monitor at B prime target for Kreisler, Exp. #572.

Results:

All successful and in half the allotted time:

1. Autoradiographs of foils at B station and just upstream of the DAS site allow reconstruction of the beam distribution anywhere between.
2. IPDIC's in the same field have a relative calibration of 7.7 to 1.
3. The carbon-eleven reaction gave 7.8×10^{13} protons on B. The calibration of the split plate sum beam monitor is 3.6×10^8 protons/count (R = 1 M, C = .003). The target used was a Be wire .050" dia. x 6" long. The telescope calibration is 8.6×10^8 protons per count, but the autoradiograph showed the beam to be larger than the target diameter.
4. The same calibration procedure gave the B prime intensity 2.4×10^{12} protons for the same run. The ion chamber calibration is 13 ion pairs per proton (2.1×10^{-18} coulombs/proton).