

BNL-104736-2014-TECH

AGS/AD/Tech Note No. 320;BNL-104736-2014-IR

THE AGS HIGH FIELD VERTICAL BUMP MAGNETS

E. Auerbach

May 1989

Collider Accelerator Department

Brookhaven National Laboratory

U.S. Department of Energy

USDOE Office of Science (SC)

Notice: This technical note has been authored by employees of Brookhaven Science Associates, LLC under Contract No.DE-AC02-76CH00016 with the U.S. Department of Energy. The publisher by accepting the technical note for publication acknowledges that the United States Government retains a non-exclusive, paid-up, irrevocable, world-wide license to publish or reproduce the published form of this technical note, or allow others to do so, for United States Government purposes.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Accelerator Division
Alternating Gradient Synchrotron Department
BROOKHAVEN NATIONAL LABORATORY
Associated Universities, Inc.
Upton, New York 11973

Accelerator Division Technical Note

AGS/AD/Tech. Note No. 320

THE AGS HIGH FIELD VERTICAL BUMP MAGNETS

E. Auerbach, E. Bleser, H. Brown

May 15, 1989

Introduction

There are two high field vertical bump magnets in the AGS. This note describes their physical and magnetic properties and shows their effects on the beam.

Description of the Magnets

The magnets are similar to magnets used in the external beam lines where they are called 6.75-D-24. They are made of an epoxy impregnated, laminated steel core, with a water-cooled, window-frame type copper coil. The dimensions and other properties are given in Table I. Note that the magnetic gap is 6.81 inches (horizontal since we are moving the beam vertically). The actual physical gap is somewhat less than this due to the epoxy coating; thus they are called 6.75-D-24 magnets, but to get good agreement between the field measurements and calculations the steel gap of 6.81 inches should be used.

In 1980 these magnets were measured using a Hall probe. Figure 1 shows B/I versus I. The measurements started at 500 Amps, went down in steps to 100 Amps, and then back to 560 Amps. The 200 Ampere point is very low, perhaps because the probe was reversed; the 100 Ampere point is a little low for reasons not understood, otherwise the calculated and measured results give good agreement. Figure 2 shows B versus I and indicates that for our purposes, the agreement between measurement and calculation is good enough; therefore, we can use the formula:

$$B[Gauss] = \frac{4\pi \text{ NI}}{10 \text{ G}} \left[\frac{Ampere-Turns}{cm} \right] = 3.487 \text{ I}[Amperes]$$

A recent calibration (J. Funaro, 3/27/89) of the command setting in the Main Control Room and the resulting current in the F-20 magnet is given in Table II and plotted in Figure 3. A good fit to this data is given by:

I[Amperes] = -8.77 + 0.0745*(Command)

Effect on the Beam for Fast Extraction

The magnets are located at F-20 and I-10. They are 50 magnets apart which in this case is a phase shift of 663 degrees. Table III shows the effects at the fast beam extraction elements. The calculations in this paper are done by MAD for P = 15 GeV/c, $Q_{\rm v}$ = 8.772.

Effect on the Beam for Slow Extraction

The slow extraction devices are the F-5 thin septum, where we often center the beam vertically, and the F-10 thick septum, which is the actual vertical aperture. Table IV shows the orbit displacements at these magnets and at H-20, the electrostatic septum. Note also that changing the vertical bumps affects the initial vertical angle of the extracted beam, best given by y' at F-10.

Since the principal use at present for the vertical bumps is to fine tune the position of the beam at F-5, we show in Table V some positions at F-5 as a function of momentum and setting, and we show the calculation below.

$$I[Amps] = -8.77 + 0.0745*(Command)$$

$$B L[T mm] = 0.266 I[Amps]$$

$$\theta[mrad] = \frac{0.3 B L}{P} \left[\frac{T mm}{GeV/c}\right]$$

$$Y(F5)[mm] = 6.36 \theta[mrad]$$

$$Y(F10)[mm] = 12.24 \theta[mrad]$$

$$Y(F5)[mm] = \frac{0.5 I}{P} [Amps/GeV/c]$$

These calculations are done by MAD for P = 15 GeV/c, Q_y = 8.772. Figures 4 and 5 show orbits calculated by MAD for P = 29 GeV/c, Q_y = 8.90. The detailed effects are somewhat different, mostly due to the vertical tune change.

Measurements

Figure 6 shows the results of applying a kick to the beam as measured by the PUE system and as calculated by MAD. The absolute agreement is very good, no doubt better than we deserve, probably resulting from some fortuitous estimates. The shape agreement is very good as we would hope. It appears that undertaking a set of careful measurements and calculations will give us a very good calibration of the vertical PUEs.

Table I

PROPERTIES OF THE VERTICAL BUMP MAGNETS

			inches		mm	
1.	Phys	sical Description				
	A. Core					
		Core Length Horizontal Steel Aperture Vertical Steel Aperture Vertical Clear Aperture	24.00 6.81 7.56 6.30		609 173 192 160	
	В.	Coil				
	0	Type - Window Frame, Water Material - Copper Total Turns No. of Pancakes Turns per Pancake Dimensions - Square Cooling Hole Diameter	0.2576 0.143	48 4 12	6.54 3.63	
	.	Locations F20, I10	0. 27		220	
_		Distance from Magnet Core	9.37		238	
2.	Resi Resi Indu	etrical Properties Astance, Measured (J. Funaro, Astance, Calculated Actance, Measured (J. Funaro, Actance, Calculated		34.5 47 2.035 2.5		
3.	Magnetic Properties					
		, Calculated , Estimated L/I, Calculated	30 105 G-in/A	3.487	G/A 762 2,667 G-mm/A	

4. Power Supply 40V, 300A

I = -8.77 + 0.0745*(Command)

Table II

CALIBRATION OF F-20 VERTICAL BUMP MAGNET

Command	Current (Amps)	Fitted Current (Amps)
100	0	- 1.3
500	27	28.5
1000	65	65.7
1500	103	102.9
2000	141	140.2
2500	178	177.4
3000	214	214.6

Table III

DISPLACEMENTS PRODUCED BY THE VERTICAL BUMPS AT THE

FAST EXTRACTION ELEMENTS

H-10 - 1.8 + 0.04

			$y_{ m mm}$	y'mr
Α.	F-20 Bump			
	= 0.3 mr			
		н-5	- 3.0	0.08
		H-10	- 0.8	0.20
В.	I-10 Bump			
	= 0.3 mr			
		H-5	- 2.7	- 0.04


Table IV

DISPLACEMENT PRODUCED BY THE VERTICAL BUMPS AT THE SLOW EXTRACTION ELEMENTS


			y mm	y' mr
A •	F-20 Bump			
	= 0.3 mr	F-5 F-10 H-20	2.0 4.0 3.8	+ 0.24 + 0.24 - 0.40
В•	I-10 Bump			
	= 0.3 mr	F-5 F-10 H-20	2.7 1.2 3.7	- 0.02 - 0.12 - 0.30

Table V
DISPLACEMENTS AT F-5 AND F-10 FOR THE F-20 BUMP

F-20 30 GeV/c 24 GeV/c Command Current Y'(F10) Y(F5) Y(F10) Y'(F10) I Y(F5) Y(F10) mrad(Amps) mmmrad \mathbf{m} mmmm0.00 0.0 0.0 0.00 0.0 0.1 100 0.0 1.2 0.08 0.5 0.9 0.06 500 28.5 0.6 2.7 0.17 1.1 2.1 0.14 1000 65.7 1.4 0.16 1100 73.1 1.5 3.0 0.19 1.2 2.4 0.27 1.7 3.3 0.22 102.9 2.2 4.2 1500 0.37 2.4 4.6 0.30 3.0 5.7 2000 140.2 0.38 3.7 7.2 0.47 3.0 5.8 2500 177.4 7.0 4.5 8.7 0.57 3.6 0.46 3000 214.6 5.3 10.2 0.67 4.3 8.2 0.54 251.9 3500 0.77 4.9 9.4 0.61 4000 289.1 6.1 11.7




Gauss/Amp



Kilogauss

 ϖ



Amperes




Figure 4a




Figure 4b




Figure 5a





Figure 5b

MEASURED VERTICAL BUMP FIG. 6



ا س