

BNL-104650-2014-TECH

AGS/AD/Tech Note No. 225;BNL-104650-2014-IR

Gas Load (Q) Measurements of the AGS Ring Vacuum Sectors

H. C. Hseuh

November 1985

Collider Accelerator Department Brookhaven National Laboratory

U.S. Department of Energy

USDOE Office of Science (SC)

Notice: This technical note has been authored by employees of Brookhaven Science Associates, LLC under Contract No.DE-AC02-76CH00016 with the U.S. Department of Energy. The publisher by accepting the technical note for publication acknowledges that the United States Government retains a non-exclusive, paid-up, irrevocable, world-wide license to publish or reproduce the published form of this technical note, or allow others to do so, for United States Government purposes.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Gas Load (Q) Measurements of the AGS Ring Vacuum Sectors

H.C. Heeuh and M(Sanki) Tanaka

07-November-85

~~~~~~~~~~

Abstract

-----

During the 1985 summer shutdown, the rate of pressure rise of each ring vacuum sector was measured several times by turning off H.V. of the ion pumps. The resulted gas load per sector,Q, varies from 1.0\*10\*\*-7 to 1.0\*10\*\*-4 torr-lit/sec.

Measurement

The gas load of each vacuum sector Q can be estimated by the sector volume V and the rate of pressure rise dP/dt such that

Q = dP/dt\*V (torr-lit/sec)

The gas load Q represents the sum of the total outgassing and leak rate of the sector.

For sectors which have no special instruments of high outgassing rate, the measured Q value is very useful in deciding the potential leaks. A change in gas load Q will also give an advanced warning of developing problem for the sector.

The rate of pressure rise was derived from cold cathode gauge reading at each vacuum sector by turning off the ion pump power supply for 10 to 20 minutes. The volume V of the standard vacuum sector is approximately 500 l while sectors A.E and G have a volume of approximately 1000 l due to special devices at their straight section and sectors AB,F,H,and HI have a volume of 2000 l due to the large boxes for beam injection and extraction.

The pressure P before turning off the ion pump H.V. and the gas load Q have been measured several times for each vacuum sector. The results are listed in Table 1. and plotted in Fig.1. Based on a single chamber measurement at the vacuum lab. the outgassing of 10 standard ring vacuum chambers (i.e. 1 sector) after one week of pumping is estimated to be approxiamately 2\*10\*\*-6 torr-1/s which is in reasonable agreement with the results for more than half of the sectors. However there are

1

Appendix.

INTERPRETATION

A: AB: Leak near B3 by VSCAN; found small leaks(10\*-8 range) at A-20 box on Oct. 14 в: Still in the process of pumping down from the B-10 cavity repair; the high outgassing of 1x10\*-4 Torr.l/s is due to the current transformer at B-5(this is consistent with the measured outgassing in lab. by V. Castillo) BC: C: May be due to the outgassing of the bump coil installed at C-13 in September CD: May have leaks around C-20 pipe D: May be due to the outgassing of the bump coil installed at D-7 in September DE: May have small leak around D-19 by VSCAN Ε: Small leak around E-9 by VSCAN EF: Area worked on in September; more ion pumps are on line No measurement due to local controlled turbo at F-10 box F: FG: Leak at G-3 bellow; found leak at F-14 bellow on Oct. 15 G: GH: Small leak near G-19 by VSCAN н: Leaks at H-12 and H-13 bellows were repaired HI: Leaks at H-16, H-17, H-19 and I-3 were found I: Small leaks were found at I-4, I-8 and I-11 IJ: May have leaks near I-17 and I-20 by VSCAN J: JK: May have leaks near K-2 by VSCAN May have leaks near K-9 by VSCAN К: KL: L: Have leaks near L-6 by VSCAN LA: May have leaks near L-17 and L-19 by VSCAN

- 3 -

P Veasurement



VACUUM SECTOR

## Q Measurement



-5 -

P (10\*\*-7 torn)

ز .